

DIVISION 1 GENERAL REQUIREMENTS

SECTION 01 5813

TEMPORARY PROJECT SIGNAGE

PART 1 – GENERAL

1.01 Summary

- A. Section includes requirements for temporary Project signage.

1.02 Project Sign (With Rendering)

- A. Provide four (4) 8 foot wide x 12 foot high x 3/4" thick project signs of exterior grade "B" or better Douglas Fir veneer permanently factory surface with a smooth, resin fiber coating and wood frame construction, painted with exhibit lettering by professional sign painter, to Owner's design and colors. Building rendering as provided. Install on three (3) 4 x 4 x 8 foot redwood posts with bottom 4 feet above finish grade and locate on site per Owner's instructions.
- B. List title of Project, names of City Council Members, City Department Heads, Bridging Architect/Construction Manager, Design-Build Team, and other information specified by Owner.
- C. Signs to be installed at specific locations directed by, and at time approved by and coordinated with, Owner. Subject to their approval, Design-Build Team should anticipate erecting signs within five (5) working days after issuance of Document 00 5500 Notice to Proceed With Construction.
- D. No other signs are allowed except those required by law.

PART 2 – PRODUCTS – NOT USED

PART 3 – EXECUTION – NOT USED

END OF SECTION